No.	Item of work	Per	Quantity
	Constructing Relieving weir.		
1	Earthwork excavation	C.yd.	17
2	Stone jelly surki concrete	C.ft.	88
3	Burnt brick in surki mortar	,,	138
4	Burnt stone slabs 6" thick roughly dressed including cement pointing.	S.ft.	50
5	Surki plastering	Sqr.	0·79
6	Rough stone work new with jelly backing and wedging ...	C.yd.	16
	Constructing a super passage at C. S. No. 30.		
1	Earthwork excavation	C.yd.	49
2	Stone jelly concrete in surki mortar	C.ft.	168
3	Burnt brick in surki mortar	,,	1,435
4	Burnt stone slabs one line dressed and fixing including cement pointing.	S.ft.	388
5	Plastering with surki mortar	Sqr.	9·55
6	Pointing with cement	,,	1·10
7	Rough stone work new with jelly backing and wedging ...	C.yd.	37

Abstract Notification dated 26th March 1933.

The attention of public is invited to the notification inviting tenders for the Construction of a New Tank near Kannaikan Agrahara Village of Anekal Taluk, published on pages 379 and 380, Part VI of the *Mysore Gazette*, dated 6th April 1933. The last date for the receipt of tenders is 24th April 1933 (at 2 P.M.) and earnest money to be deposited is Rs. 250.

H. F. MARKER,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

No. 1688, *dated 25th March* 1933.

The attention of the public is invited to the Notification dated 22nd March 1933, calling for tenders for "Improving the Water Supply Scheme to the Robertsonpet" published on pages 378 and 379, Part VI of the *Mysore Gazette*, dated 6th April 1933. The last date for receipt of tenders is 15th April 1933.

B. R. GARUDACHAR,
Executive Engineer.

TUMKUR DIVISION

Abstract Notification, dated 28th March 1933.

Subject.—

Opening a road from Gubbi to Chitnahalli or Chandrasekharapura in Gubbi Taluk.

Attention of the public is drawn to the notification calling for tenders for the above work in page 382 and 383, Part VI of the *Mysore Gazette*, dated 6th April 1933.

2. The tenders will be received by the Executive Engineer, Tumkur Division, Tumkur, up-to 3 P.M. of 26th April 1933.

3. An earnest money of Rs. 700 should accompany the tender.

N. G. KRISHNA IYENGAR,
Executive Engineer,

KOLAR DIVISION.

Notification dated 12—13th April 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., 2nd May 1933, for Restoring Mallandahally Doddakere, Registered No. 151—877 of Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred only in cash or Government Currency Notes, as earnest money, and be superscribed " Tender for the work of restoring Mallandahalli Doddakere, Registered No. 151—877 of Kolar Taluk," in default of which the tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for restoring Mallandahalli Doddakere, Registered No. 151—877 in Kolar Taluk.

Sl. No.	Items of work	Unit	Rate	Quantity	Cost
	Bund.		Rs. a. p.		Rs.
1	Clearing prickly pears and jungle growth and roots, etc., entirely grubbed up.	Grade	3 0 0	20	60
2	Removing ant hills and filling with sand ...	,,	1 0 0	20	20
3	Earthwork to bund with watering and tamping.	C.yd.	0 4 0	4428	1,107
3a	Earth available from excavation of weir ...	,,	0 1 0	30	2
4	Clearing sand from the seat of bund and filling in pits rear of bund beyond near slope.	,,	0 2 0	198	25
5	Turfing	S.yds.	0 1 0	4313·42	269
6	Earthwork cutting trenches ...	C.yd.	0 4 0	48	12
7	Refilling with good clay puddle ...	,,	0 6 0	48	18
8	New stone work with jelly backing and wedging.	,,	1 12 0	831	1,454
9	Removing and resetting old stone work with jelly backing and wedging.	,,	0 10 0	401	251
10	Providing and fixing new grade stones including chistelling and painting.	No.	1 8 0	21	32
11	Do new register, No. and date stones cutting figures and painting.	,,	5 0 0	1	5
12	Do gauge stones cutting figures and painting.	,,	10 0 0	1	10
13	Painting old B. M. stones	,,	0 8 0	2	1
14	Providing, painting and fixing new index stones.	,,	0 8 0	21	11
15	Gravel backing to revetment ...	C.yd.	0 6 0	350	175
15a	For ramp and top of bund to rear of sluice.	,,	0 6 0	118	
	Total ...	..	...	....	3,452

Sl, No.	Items of work	Unit	Rate	Quantity	Cost
	Sluice at 43·50		Rs. a. p.		Rs.
1	Earthwork to bund cut opening ...	C.yd.	0 3 0	116	22
2	Do Refilling	,,	0 3 0	116	22
2a	Mixing gravel $\frac{1}{3}$ ($^{116}/_{3}$)	,,	0 6 0	39	13
3	Putting in surki concrete	C.ft.	0 4 0	208	52
4	Burnt brick in surki mortar	,,	0 4 6	617	174
	Plastering with surki mortar ...	Sqr.	3 12 0	6·24	24
	Burnt stone slabs with neat joints ...	S.ft.	0 5 0	1·91	60
	Total ...	...	...	...	367
	Constructing a Waste Weir 85 *feet long.*				
1	Earth work excavation in gravelly soil and forming ramp in front and filling the scour.	C.yds.	0 4 0	21	5
2	Putting in surki concrete (stone jelly in surki) concrete.	C.ft.	0 4 0	103	26
3	Burnt stone in surki mortar	,,	0 5 0	236	74
4	Pointing in cement	Sqrs.	4 0 0	4·32	17
5	Burnt stone slabs	S.ft.	0 5 0	230	72
6	Joggle joints	No.	1 0 0	8	8
7	Excavating foundation for apron and using soil to bund chargeable to bund.	...	...	...	...
8	Rough stone work with jelly backing and wedging.	C.yd.	1 12 0	29	51
	Total ...	...	...	...	253
	Rs. 3,452+367+253=Rs. 4,072 Total Bund, Sluice and Weir.	...	...	...	4,072

C. T. NARASIMHA IYENGAR,
Executive Engineer.

KADUR DIVISION.

Abstract Notification, dated 5th April 1933.

The attention of the public is invited to the notice calling for tenders for the improvement to Educational buildings (Old District Hospital) at Chikmagalur, published in pages 406-408 part VI of *Mysore Gazette* of 15th April 1933. The last date for receiving tenders is 22nd April 1933. Earnest money to be furnished is Rs. 75.

Abstract Notification.

The attention of the public is invited to the Notice calling for tenders for layout of Sanigere-Huligere road, published on page 405 of part VI of *Mysore Gazette* of 13th April 1933.

The last date for receiving tenders is 1st May 1933 Earnest money to be furnished is Rs. 110.

Abstract Notification.

Attention of the public is invited to the notification in the *Mysore Gazette*, dated 13th April 1933, *re* sale of fishery of Ayyankere tank, Kadur Taluk. The date of sale is fixed for 28th April 1933.

Notification.

It is hereby notified for the information of the general public that the right of fishery of Ayyanakere Tank, Kadur Taluk, will be sold by public auction on Friday the 28th April 1933, by the Assistant Engineer, Kadur Sub-Division. Intending bidders may appear and purchase the same in the auction.

L. A. H. WINCKLER,
Executive Engineer.